DAYHUFF ESTATES MINOR PLAT

PART OF THE NORTHEAST QUARTER OF SECTION 17, TOWNSHIP 13 NORTH, RANGE 2 EAST, MORGAN COUNTY, INDIANA

OWNERS & DEVELOPERS
MARTIN WITTE & OYCIE HENDERSON
P.O. BOX 41, MOORESVILLE, IN. 46158

DEDICATION OF DAYHUFF MINOR PLAT

The undersigned, Martin Witte and Oycie Henderson, owners of the real estate shown and described hereon, do hereby certify that they have platted and subdivided the same into four (4) lots to be known as Dayhuff Estates Minor Plat, and do hereby establish the following dedications upon all covenants and restrictions to run with the land and to be binding upon all future owners, heirs and assigns:

1. Each of the lots hereby created shall be subject to the covenants and restrictions as shown and recorded hereon, in addition to those rules, regulations or conditions as required by Agencies of the Town of Mooresville, Morgan County or any other government entities.
2. The twenty-five (25) foot wide strip along the north side of the subject parcel, shown hereon as right-of-way, is hereby dedicated to the public for roadway purposes.
3. The shared private road within the fifty (50) foot wide access and utility easement along the east line of this Minor Plat is to be used by the owner's of Lot 2, Lot 3 and Lot 4 and maintained on a share and share alike basis by those lot owners.

This declaratory statement of certification and approval to run with the land is hereby so declared and executed this 26 day of August, 2005.

Martin Witte

Oycie Henderson

State of Indiana)
)
County of Morgan)

Before me, the undersigned, a Notary Public, personally appeared

Martin Witte and Oycie Henderson and acknowledged the execution of this instrument to be their voluntary act and deed.

Witness my Hand and Seal this 26 day of August 2005.

Signed Notary Public

Rois O. Holloway
Printed or Typed

Resident of Morgan County.

My Commission Expires: 8/28/2009

MOORESVILLE PLAN COMMISSION CERTIFICATION

UNDER AUTHORITY PROVIDED BY IC-36-7-4 ENACTED BY THE GENERAL ASSEMBLY OF THE STATE OF INDIANA, AND ALL ACTS AMENDATORY THERETO, AND BY AN ORDINANCE ADOPTED BY THE TOWN COUNCIL OF TRUSTEES OF THE TOWN OF MOORESVILLE, INDIANA, THIS PLAT AND DEDICATION WAS GIVEN APPROVAL BY THE TOWN OF MOORESVILLE AT A MEETING HELD ON THE 25th DAY OF August, 2005

MOORESVILLE PLAN COMMISSION APPROVAL BY:

PRESIDENT — SECRETARY

MICHAEL L. YOUNG — DONALD E. STRIGHT
PRINTED — PRINTED

DAYHUFF ESTATES
COVENANTS AND RESTRICTIONS

This document amends covenants and restrictions for all Lots in Dayhuff Estates, a Minor Plat; Lying in part of the Northeast Quarter of Section 17, Township 13 North, Range 2 East, Morgan County, Indiana.

All purchasers, their heirs and assigns, of Lots in Dayhuff Estates, shall take title subject to the following covenants and restrictions and shall be bound thereby.

1. Land Use. All parcels herein are for residential use only, limited to a single family dwelling per parcel. There shall be no further division of any lot in Dayhuff Estates.
2. Drainage. Owner of each parcel shall take their title subject to the rights of others to use the natural ravines, swales and valleys for the conveyance of stormwater. No owner shall impede or hinder, in any way, the passage of stormwater through or across their lot. Each owner shall provide acequate structures to convey stormwater where improvements are constructed across swales, valleys, and ravines.
3. Signs. No sign of any kinc Shall be displayed to the public view on any lot except for one sign of not more than five (5) square feet advertising the property for sale or rent. No more than four (4) signs no larger than five (5) square feet shall be allowed by builder or others to advertise the property during construction; however, any sign required by law may be displayed during the construction period in addition to the permitted signs. This covenant has no application to marketing or promotional signs of the developer while lots are being sold.
4. Vacant Lot Maintenance. No trash shall be allowed to accumulate on any parcel in this unplatted division. If sold lots are not maintained, the developer shall have the option to maintain the property, by removing trash or debris and charge the owner a reasonable fee.
5. Storage and Refuse Disposal. No outside storage of equipment, materials, supplies, debris and unlicensed or inoperative vehicles, (including unlicensed or inoperative recreation vehicles or boats) shall be permitted. Trash, garbage or other wastes shall not be kept except in sanitary containers. All equipment for the storage of such materials shall be kept in a clean and sanitary condition. No incinerators or trash burning shall be allowed.
6. Animals. No livestock or poultry of any kinc shall be raised, bred or kept on any lot. All animals shall be restricted to owners' property unless the animal is on a leash accompanied by the owner. No animals of any type shall, be kept or bred.
7. Nuisance. No noxious or offensive activity of any kinc shall be suffered or permitted to continue which may annoy or become a nuisance to a neighbor or the neighborhood, nor shall any unlawful act or activity be allowed whatsoever.
8. Auto Mechanics. Except for minor or routine repair and maintenance of the owners' personal vehicles, no welding, restoration, reconstruction, overhauling, painting or other type of auto mechanics, whether, for hire or otherwise, shall be permitted
9. Architectural Design. The developer shall review and approve all plans for the construction of residential dwelling houses and accessory buildings to promote harmony of design and compatibility with existing structures. The developer also shall approve any technical variation or exception from any construction requirements. No reasonable design may be denied.
10. Dwelling Restrictions. No mobile home, trailer or other portable device or outbuilding, garage or basement shall be used as residence. This provision shall not be construed to prevent a builder from using such for material or tool storage or office during the period of construction or a temporary office for developer's marketing or promotional purposes.
11. Building Type. No dwelling shall exceed two and one-half (2 ½) stories in height. One (1) residential accessory building shall be allowed per parcel. The accessory building shall not exceed 1000 square feet in size, and said accessory building shall be of similar/complimentary construction materials as the dwelling structure on that parcel.
12. Dwelling Quality and Size. The ground floor of the dwelling structure, exclusive of porches, basements and garages, shall be not less than one-thousand five-hundred (1800) squares feet for a one-story dweling not less than one-thousand two hundred (1200) square feet for a dwelling of more than one-story, with a minimum of four-hundred (400) square feet on the second levels. The first story of the dwelling shall be full brick/masonry construction. The second story of each dwelling be a balanced fifty per cent (50 %) brick/masonry construction. Exceptions to masonry requirements shall be made at the discretion of the developer.
13. Construction Requirements.
    a. Overhang (eaves) shall be a minimum of twelve (12) inches, excluding any exterior finish.
    b. The roof shal have a minimum of 6/12 pitch and shingles shall be asphalt, cedar or fiberglass.
    c. After construction, all lots shall be graded and landscaped. The grading shall be so as to provide positive drainage from the house as constructed. To insure positive drainage the ground shall slope away from the dwelling a minimum of one (1) inch per foot, for the first six (6) feet outside the perimeter of the foundation, or as determined by the developer, considering specific lot characteristics.
    d. All construction, finish grading, sidewalks and landscaping shall be completed within one (1) year of the start of construction, acts of God and unusual weather or destruction of work in progress excepting.
    e. All owners and their builders/contractors shall be responsible for and maintain the job site in a reasonable, sightly order, containing all trash and debris within the lot and property disposed of or removed.
    f. All owners and their builders/contractors shall be responsible for and repair or restore any damage during construction, whether or not inadvertent or unavoidable.
14. Erosion and Sediment Control. Each owner and their builders/contractors shall be responsible for erosion and sediment control on their lot in accordance, with Title 327, Article 15, Indiana Administrative Code, commonly referred to as "Rule 5". Erosion and sediment control measures shall include but are not limited to: silt fencing, storm inlet protection, bank protection with erosion control blankets, sodding, mulch seeding and/or a combination thereof. If the Developer, or any duly authorized agency of State or Federal Government finds that an owner or their builder/contractor has not taken adequate erosion and sediment control measures then appropriate action will be taken against the lot owner or their builder/contractor to enforce compliance with this provision.
15. Enforcement. The right to enforce these covenants by injunction or to seek damages for violation or other remedy is dedicated to the owners of the lots herein and the developer. The covenants and restrictions shall remain in full force and unchanged in perpetuity unless otherwise agreed by a two-thirds vote of lot owners, one vote for each lot owned. Invalidation of any covenant or restriction herein by judgment, court order or otherwise, shall not affect any other covenant or restriction. Violation of a covenant or restriction shall not cause forfeiture or reversion of title.

DESCRIPTION OF DAYHUFF ESTATES MINOR PLAT

Part of the Northeast Quarter of Section 17, Township 13 North, Range 2 East, Morgan County, Indiana, described as follows:

Commencing at an iron pin with aluminum cap found per the county records, in the county road which marks the Northeast corner of the Northeast Quarter of Section 17; thence with the North Line of the above captioned quarter section, and in the county road, South 87 degrees 49 minutes 45 seconds West (assumed bearing), 689.61 feet to an iron survey nail with washer engraved "Holloway F. N. 46, and the POINT OF BEGINNING of the Dayhuff Minor Plat herein described; thence continuing with said North Line and in the county road, South 87 degrees 49 minutes 45 seconds West, 628.97 feet to a point referenced by an iron spike found North no degrees 36 minutes 07 seconds West, 0.58 feet; thence South no degrees 36 minutes 07 seconds East, 438.99 feet, to a iron pin set with cap engraved "Holloway Engr Firm No. 46"; thence North 87 degrees 49 minutes 45 seconds East, 263.49 feet to an iron pin set with cap engraved "Holloway F. N. 46"; thence South 25 degrees 52 minutes 31 seconds West, 85.34 feet, to an iron pin set with cap engraved "Holloway Firm No. 46"; thence North 87 degrees 49 minutes 45 seconds East, 79.57 feet to an iron pin set with cap engraved "Holloway Engr Firm No. 46"; thence South no degrees 35 minutes 31 seconds East, 621.09 feet (a record distance of 621.00 feet) to an iron pin found; thence South 87 degrees 51 minutes 30 seconds West, 331.25 feet (a record distance of 330.00 feet to a point referenced by an iron pin found North 90 degrees no minutes no seconds East, 1.27 feet; thence South no degrees 32 minutes 31 seconds East, 357.63 feet to an iron pin set with cap engraved "Holloway F. N. 46"; thence North 81 degrees 29 minutes 22 seconds East, 660.26 feet to an iron pin set with cap engraved "Holloway F. N. 46"; thence North no degrees 32 minutes 31 seconds West, 1419.98 feet to the point of beginning.

Containing 16.423 acres more or less, and subject to the right-of-way for the county road along the North Line of the parcel and to any other right-of-ways, easements or restrictions of record or observable.

DULY ENTERED FOR TAXATION
Subject to final acceptance for transfer

SEP 06 2005

Auditor, Morgan County

MORGAN COUNTY RECORDER
KAREN BRUMMETT
PID Date 09/06/2005 Time 13:48:20
RECORDING: 118.00
1 2005122553 Page 1 of 1

OWNER OF RECORD:
MARTIN WITTE AND OYCIE HENDERSON PER INSTRUMENT NUMBER 200500489
THERE ARE NO IMPROVEMENTS ON THE LOTS


1" I. PIPE FOUND, ACCEPTED NW COR., NE-1/4, SEC. 17 S 87°49'45" W - 2706.12'
CAL COR. (EXCEPTION) I. SPIKE FOUND N 00°36'07" W - 0.58'
DAYHUFF ROAD
POINT OF BEGINNING
S 87°49'45" W 689.61'
1. PIN W/ALUM. CAP FOUND PER COUNTY RECORDS NE COR., NE-1/4 SEC. 17
3/4 MILE ± TO THE INTERSECTION OF DAYHUFF ROAD & KITCHEN ROAD.
628.97'
472.62'
156.33'
CALCULATED CORNER OF PARENT PARCEL DR 372 PG 144 AND EXCEPTION OUT OF PARENT PARCEL, AND EAST LINE OF ADJOINING PARCELS TO THE WEST; ALL CALLING FOR A DISTANCE OF 1340.78 FEET FROM THE NE COR. SEC. 17 (I. SPIKE FOUND- N 28°36'36" E - 0.44')
Lot 1 3.497± Ac
Lot 2 3.140± Ac
Lot 3 3.000± Ac
Lot 4 6.425± Ac
PHARIS DR 407 PG 109
JONES DR 337 PG 105 5.017± Ac
JACOBS DR 372 PG 144
HARE DR 176 PG 521 21.863± Ac
S 00°36'07" E - 438.99'
N 87°49'45" E - 263.49'
S 87°49'45" W - 403.01'
323.44'
S 87°49'45" W 323.06'
S 00°35'31" E - 621.09'
N 00°32'31" W - 1419.98'
S 00°32'31" E - 357.63'
S 87°51'30" W - 331.25'
N 81°29'22" E - 660.26'
N 81°29'22" E - 1356.31' (1354.32' REC.)
686.05'
1356.98'
S 00°32'31" E - 1419.98'
50' R.O.W & U/E
20' U-E
40' B.L.
25' B.L.
50' WIDE PROPOSED STONE ROAD
50' WIDE A.& U.-E
20' WIDE PROPOSED STONE ROAD
S 27°05'31" W - 504.23'
466.88'
489.35'
404.41'
404.43'
WOODED AREA
IRON PIN FOUND PER DESCRIPTION
IRON PIN FOUND PER LEGAL DESC. N 90°00'00" E - 1.27'
IRON PIN FOUND PER LEGAL DESC. N 00°36'00" W - 3.06' N 48°42'38" W - 2.2'
(330.00' R)
(621.00' R)
SEPTIC EASEMENT #1-LOT 3
SEPTIC EASEMENT #2- LOT 3
SEPTIC EASE. #1- LOT 4
SEPTIC EASE. #2- LOT 4
N 87°49'45" W - 130.00'
N 00°36'00" W - 130.00'
S 87°49'45" W 130.00'
S 00°36'00" E 130.00'
S 87°49'45" W 130.00'
N 87°49'45" W - 130.00'
S 87°49'45" W 143.08'
S 87°49'45" W 102.43'
S 87°49'45" W 79.30'
S 87°49'45" W 50.40'
S 87°49'45" W 38.07'
S 87°49'45" W 37.90'
N 87°49'45" W 37.90'
N 87°49'45" W 79.30'
N 87°49'45" W 102.43'
N 87°49'45" W 143.08'
N 87°49'45" W 158.17'
N 87°49'45" W 158.17'
N 87°49'45" W 86.85'
N 87°49'45" W 79.57'
N 87°49'45" W 50.40'
S 00°36'00" E 130.00'
S 00°36'00" E 130.00'
S 00°36'00" E 130.00