

FARHILL DOWNS - Section Seven

I, the undersigned Registered Land Surveyor, do hereby certify that the within plat is true and correctly represents a subdivision of a part of the Southeast quarter of Section 34, Township 15 North, Range 4 East in Marion County, Indiana, said part being more particularly described as follows:

Beginning at the Northwest corner of said Southeast quarter section; thence North 88 degrees 54 minutes 23 seconds East upon and along the North line of said quarter section 143.92 feet to a point, said point being the Northwest corner of Lot 12 in Farhill Downs, Section One, as per plat thereof recorded as Instrument Number 73-38686 in the office of the Recorder of Marion County, Indiana; thence southerly and westerly along the western boundary of said Section One by the following bearings and distances: South 01 degrees 28 minutes 58 seconds West 203.33 feet; South 20 degrees 00 minutes 00 seconds West 195.18 feet; South 90 degrees 00 minutes 00 seconds West 110.90 feet; South 56 degrees 14 minutes 15 seconds West 97.08 feet; South 45 degrees 00 minutes 00 seconds West 471.38 feet; South 13 degrees 10 minutes 05 seconds West 88.89 feet to a point, said point being the Northwest corner of Lot 326 in Farhill Downs, Section Six, as per plat thereof recorded as Instrument Number 75-27869 in the office of the Recorder of Marion County, Indiana; thence westerly along the northern boundary of said Section Six, by the following bearings and distances: North 75 degrees 00 minutes 00 seconds West 333.58 feet; South 90 degrees 00 minutes 00 seconds West 510.67 feet; South 78 degrees 33 minutes 32 seconds West 50.39 feet; North 89 degrees 58 minutes 15 seconds West 155.12 feet to a point on the West line of aforesaid Southeast quarter section; thence North 00 degrees 01 minutes 58 seconds West upon and along said West line 749.84 feet to the place of beginning, containing in all 25.544 acres, more or less, subject, however, to all legal highways, rights-of-way, easements and restrictions of record.

This subdivision consists of 77 lots numbered consecutively from 384 to 453 (both inclusive) and an area designated block "A". The size of the lots and widths of the streets are shown in feet and decimal parts thereof.


CERTIFIED: May 23, 1977

R. V. Cooper, Clerk
Registered Land Surveyor
No. 1131


LEGEND
(12,345) SQUARE FEET
[234] ADDRESS

Block "A", shown shaded on this plat, depicts a special restricted area. See covenant #7a for details.

RECEIVED FOR RECORD
 RECORDER'S BYRD
 RECORDER, MARION CO
 AUG 3 1 32 PM '77



Stoepfelwerth
Registered Land Surveyor
No. 1131



LEGEND
 (12.345) SQUARE FEET
 [1234] ADDRESS

Block "A", shown shaded on this plat, depicts a special restricted area. See covenant #7a for details.

RECEIVED FOR RECORD
 REC'D US BY RD
 REC'DER-MARCH 05
 AUG 5 1 33 PM '71



CURVE	1-A	21FO
1-A	21FO	21FO
2-A	46FO	46FO
2-B	46FO	46FO


This instrument prepared by R. M. Stoepfelwerth.

STOEPFELWERTH & ASSOC
 CONSULTING ENGINEERS
 INDIANAPOLIS, INDIANA

SHEET NO.

50.09
et to a
ection;
d along
taining
legal
rd.

iv from
' The
et and



CURVE DATA

CURVE	Δ	R	L	T	D
1-A	21°05'37"	250.00'	92.04'	46.546'	22.91831°
1-B	21°05'37"	275.00'	101.24'	51.201'	20.83483°
2-A	21°05'37"	300.00'	110.45'	55.855'	19.09859°
2-B	46°05'37"	200.00'	160.90'	85.088'	28.64789°
2-C	46°05'37"	225.00'	181.01'	95.724'	25.46479°
2-D	46°05'37"	250.00'	201.12'	106.360'	22.91831°

August 3, 1977
Tom Featherston

STOEPPELWERTH & ASSOCIATES
CONSULTING ENGINEERS

INDIANAPOLIS, INDIANA

6-23-77 Sub 5 J.L. Lots 305-386 CLM OF BY


Seven

certify
 nts a
 on 34,
 s, said
 quarter
 st upon
 t to a
 'arhill
 rument
 ounty,
 undary
 South
 South
 South
 South
 legress
 legress
 being
 .i.x, as
 n the
 sterly
 lowing
 econds
 West
 50.99
 t to a
 ction;
 along
 aining
 legal
 d.

to iron
 the
 set and

ARE FEET
 PRESS

770019061



N LINE SE 1/4 SEC 34-T15N-R4E
 NW COR SE 1/4 SEC 34-T15N-R4E
 N 88°54'23"E
 154278
 RIDGE DRIVE
 101706
 N 88°54'23"E
 180444

19264

FARHILL DOWNS

DEDICATION, RESTRICTIONS, AND PROTECTIVE COVENANTS

2. the undersigned, Douglas R. Whitson and Dorothy A. Whitson, his wife, owners of the real estate described in the foregoing Land Surveyor's Certificate do hereby certify that they lay off, plat and subdivide the same in accordance with the within plat. This subdivision shall be known and designated as Farhill Downs, Section Seven.

3. Dedication: All streets shown and not heretofore dedicated are hereby dedicated to the public as right-of-way for public streets.

4. Land Use and Building Type: No lot shall be used except for residential purposes. No building shall be erected, altered, placed, or permitted to remain on any lot other than one detached single-family dwelling not to exceed two and one-half stories in height and a private garage for not more than three cars. No structure shall exceed 35 feet in height.

5. Architectural Control: No building shall be erected, placed, or altered on any lot until the construction plans and specifications and a plan showing the location of the structure have been approved by the Architectural Control Committee as to quality of workmanship and materials, harmony of external design with existing structures, and as to location with respect to orientation and finish grade elevations. No fence or wall shall be erected, placed, or altered on any lot nearer to any street than the minimum building setback lines unless similarly approved. Approval shall be as provided in paragraph #13 below.

6. Dwelling Quality and Size: The ground floor area of the main structure, exclusive of one-story open porches and garages, shall be not less than 1200 square feet, in the case of a one-story dwelling, nor less than 400 square feet of ground floor area for a dwelling more than one story in height. The vertical exterior walls of the first story of all dwellings shall be composed of at least twenty percent (20%) clay-brick or stone.

7. Building Location: No building shall be located on any lot nearer to the front lot line or nearer to the side street line than the minimum building setback lines shown on the recorded plat. No dwelling shall be located nearer than six feet to any side lot line. No building shall be located nearer than 20 feet to any rear lot line. For the purpose of this covenant, overhanging eaves to a 4-foot maximum shall not be considered as a part of the building; provided, however, that this shall not be construed to permit any portion of a building on a lot to encroach upon another lot.

8. Lot Area and Width: No dwelling shall be erected or placed on any lot having a width at the minimum building setback line of less than the minimum required in a 2-3 zoning district, nor shall any dwelling be erected or placed on any lot having an area, of less than the minimum required in a 2-3 zoning district.

9. Easements: Easements for installation and maintenance of utilities and drainage facilities are reserved as shown on the recorded plat. Right of access and ingress for maintenance shall not be prohibited. No permanent or other structure shall be erected or maintained upon said easement. No bushes, trees, etc. are to be planted within drainage easements that will obstruct the flow of storm water. Furthermore, no driveway shall be allowed to cross a planting easement. Easements for emergency access are reserved as shown on the recorded plat. No permanent or temporary structures, fences, trees, bushes, etc., shall be erected, planted or maintained upon said easements.

10. Subsidence: No noxious or offensive activity shall be carried on upon any lot, nor shall any type of noise emanate which may be or may become an annoyance or nuisance to the neighboring lot. No recreational or unlicensed vehicle shall be parked on or repaired on any lot in this subdivision or on any street, thereof. No boat, trailer, or camper shall be stored within 20 feet of the front property line of any lot.

11. Temporary Structures: No structure of a temporary character, trailer, easement, tent, shade, garage, barn, or other outbuilding shall be used on any lot at any time as a residence, other temporarily or permanently.

a D-3 zoning district, nor shall any building be erected or placed on any lot having an area of less than the minimum required in a D-3 zoning district.

Easements: Easements for installation and maintenance of utilities and drainage facilities are reserved as shown on the recorded plat. Right of ingress and egress for maintenance shall not be prohibited. No permanent or other structure shall be erected or maintained upon said easement. No bushes, trees, etc. are to be planted within drainage easements that will obstruct the flow of storm water. Furthermore, no driveway shall be allowed to cross a planting easement. Easements for emergency access are reserved as shown on the recorded plat. No permanent or temporary structures, fences, trees, bushes, etc., shall be erected, planted or maintained upon said easements.

Nuisances: No noxious or offensive activity shall be carried on upon any lot, nor shall anything be done thereon which may be or may become an annoyance or nuisance to the neighborhood. No unoperative or unlicensed vehicle shall be parked on or repaired on any lot in this subdivision or on any street thereof. No boat, trailer, or camper shall be parked within 20 feet of the front property line of any lot.

Temporary Structures: No structure of a temporary character, trailer, basement, tent, shack, garage, barn, or other outbuilding shall be used on any lot at any time as a residence, other temporary or permanently.

→* 4. Block "A" Special Restricted Area

Block "A", shown shaded on the plat, depicts a special restricted area. This area contains a storm water retention basin specially constructed to detain storm water for short periods of time during and after a rain. No building, planting, regrading, fencing, dumping, etc., shall be permitted within this area.

Section Seven

Livestock and Poultry: No animals, livestock, or poultry of any kind shall be raised, bred or kept on any lot, except that dogs, cats, or other household pets may be kept provided that they are not kept, bred, or maintained for any commercial purposes.

11. Garbage and Refuse Disposal: No lot shall be used or maintained as a dumping ground for rubbish. Trash, garbage, or other waste shall not be kept except in sanitary containers. All incinerators or other equipment for the storage or disposal of such material shall be kept in a clean and sanitary condition.

12. Sight Distance at Intersections: No fence, wall, hedge or shrub planting which obstructs sight lines at elevations between two and six feet above the roadways shall be placed or permitted to remain on any corner lot within the triangular area formed by the street property lines and a line connecting them at points 25 feet from the intersection of the street lines; or, in the case of a rounded property corner from the intersection of the street property lines extended. The same sight line limitations shall apply on any lot within 10 feet from the intersection of a street property line with the edge of a driveway. No tree shall be permitted to remain within such distances of such intersection unless the foliage line is maintained at sufficient height to prevent obstruction of such sight lines.

13. Architectural Control Committee: The Architectural Control Committee is composed of Douglas R. Whitson, O. Kenneth Baird, and Charles Fleitz of Indianapolis, Indiana. A majority of the Committee may designate a representative to act for it. In the event of death or resignation of any member of the Committee, the remaining members shall have full authority to designate a successor. Neither the members of the Committee nor its designated representative shall be entitled to any compensation for services performed pursuant to this covenant. The powers and duties of such Committee and of its designated representative shall cease on and after 25 years from date of plat. Thereafter, the approval described herein shall not be required unless prior to said date and effective thereon, a majority of the lot owners in this subdivision appoint a representative or representatives who shall thereafter exercise the same powers previously exercised by said Committee. The Committee's approval or disapproval as required in these covenants shall be in writing. In the event the Committee, or its designated representative fails to approve or disapprove within 30 days after plans and specifications have been submitted to it, or in any event if no suit to enjoin the construction has been commenced prior to the completion thereof approval will not be required and the related covenants shall be deemed to have been fully complied with.

14. Waiver of Right to Remonstrate Against Annexation: No lot owner shall remonstrate against or otherwise in any way object to or commence or otherwise be party to any legal proceedings to prevent any action taken by the Common Council of the City of Indianapolis, Indiana, to annex or otherwise incorporate within the boundaries of said City all or any portion of said Addition to said City of Indianapolis, Indiana, pursuant to any existing or future statute or other law of the State of Indiana or otherwise.

The foregoing dedication, restrictions, and protective covenants are to run with the land and shall be binding on all parties and all persons claiming under them until 25 years from date of plat, at which time said covenants, or restriction, shall be automatically extended for successive periods of ten (10) years unless changed by vote of the majority of the then owners of the building lots covered by these covenants, or restrictions. Invalidation of any one of these covenants by judgment of a court of competent jurisdiction shall in no wise affect any other covenant or restriction, which shall remain in full force and effect. The right to enforce the within provisions, restrictions, and covenants by injunction together with the right to cause removal by due process of law of structures erected or maintained in violation thereof, is hereby dedicated and reserved to the owners of the several lots in this subdivision.